



**S.N.D.T. Women's University**  
**Sir Vithaldas Thackersey College of Home Science**  
**(Autonomous)**



NAAC Re-accredited 'A' Grade  
UGC Honor - College with Potential for Excellence

SVT/Quotation/2019-20/133

Date: 04.05.2019

SUB: Quotation for Proposed Alteration and Renovation Work for Admin Service Block Work under RUSA -2 Infrastructure grant at Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai.

Madam /Sir,

Sealed quotations are invited for Proposed Alteration and Renovation Work for Admin Service Block Work under RUSA -2 Infrastructure grant at Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai. Interested vendors are requested to submit their quote in the format given in Annexure A on company letter head. Quotation should be submitted to The Principal, Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai on or before 10<sup>th</sup> May , 2019 (before 4.00 p.m.)

Sir Vithaldas Thackersey College of Home Science (Autonomous), SNDT Women's University, Santacruz (West), Mumbai reserves the right to reject any or all quotations without assigning any reasons thereof.

  
Dr. Jagmeet Madan  
(Principal)

(Offer should filled on letter head)  
Annexure A

To,  
The Principal,  
Sir Vithaldas Thackersey College of Home Science (Autonomous),  
SNDT Women's University,  
Juhu, Santacruz (West),  
Mumbai - 400 049.

SUB: Quotation for Proposed Alteration and Renovation Work for Admin Service Block Work under RUSA -2 Infrastructure grant at Sir Vithaldas Thackersey College of Home Science (Autonomous) SNDT Women's University, Sir Vithaldas Vidyavihar Campus, Juhu Tara Road, Santacruz (West), Mumbai.

Respected Sir / Madam,

With reference to subject cited above we would like to furnish our quote with best rate possible as below :

SR.NO	PARTICULARS	UNITS	QTY	RATE Per Sqft	AMOUNT
1	<b>Admin Area :-</b>				
1.1	<b>Breaking/Removing :-</b> All bathroom wall & floor tile and bathroom accessories.	Sq.Ft	300 Sqft		
1.2	<b>Leveling Pcc work :</b> Providing and laying Brick bat coba 9" deep and P/L sand and cement in the ratio of 6:1 for P.c.c work.	Sq.Ft	45 Sqft		
1.3	<b>Waterproofing :-</b> P / A Water-proofing treatment to bathroom area surfaces consisting of 2 coats of Dr. Fixit base coat to floors and vertical sides upto 900mm High from finish floor as under. Ist & 2nd coat of (Dr. fixit 301 Pidicrete URP) mixed with grey cement sealing all junctions, corners, joints of pipes and concrete.(allow for necessary curing and drying time of each coat, including surface preparation, cleaning the existing flooring, covering the waterproofing by plastering on top and bottom.	Sq.Ft	125 Sqft		



1.4	<b>Plaster :-</b> Providing & laying new plaster with sand and cement	Sq.Ft	210 Sqft		
1.5	<b>Wall Tiling :</b> 2'X2' , approximately 25mm thk tile fixing in bathroom, to be laid as per design, using 1:4 cement mortar, with machine cutting as required, joints treated with neat laticrete with an admixture of pigment as per drawing, to be laid as per plan complete, (base rate 85/-)	Sq.Ft	210 Sqft		
1.6	<b>Floor Tiling :</b> 2'X2' , approximately 25mm thk tile fixing in bathroom, to be laid as per design, using 1:4 cement mortar, with machine cutting as required, joints treated with neat laticrete with an admixture of pigment as per drawing, to be laid as per plan complete, (base rate 85/-)	Sq.Ft	45 Sqft		
1.7	<b>Plumbing :-</b> PVC pipe of Prince or comparable brand, laying and looping for water supply with soil and drain pipes laid in slope for wet and dry areas of toilet.	Sq.Ft	1 Sqft		
1.8	<b>Bathroom Accessories :-</b> Providing & fixing bathroom accessories Jaqure brand fitting.	L/s	1 Sqft		
1.9	<b>Counter :-</b> Providing & fixing bathroom basin counter 50mm thick tile with mortar cement.	R.ft	3 Sqft		
2.0	<b>Under Counter Storage :-</b> Providing & fixing basin counter under storage in 19mm thick MR Ply with laminate finish.	Nos	1 Sqft		
2.1	<b>Electrical Work :-</b> New electrical work done in 1.5mm thk Polycap or comparable grade wire with ROMA or comparable brand switches as specified by architect.				
2.2	New electrical work done in 1.5mm thk Polycap or comparable grade wire for new light fittings as specified by architect.	L/s	1 Sqft		

2.3	<b>Paint Work :-</b> Applying on wall three coats of <u>Off white Luster Paint</u> of approved brand to give an even shade and colour after thoroughly brushing the surface, clean of all greaze and dirt, loose pieces of seals including preparing the surface with sand paper smooth ( complete job including cost of materials and labour)	Sq.Ft	150 Sqft			
2.5	<b>Repair Work :-</b> Bathroom Existing Door & door frame repairing with aluminium composite panel sheet finish bathroom door inside & outside existing veneer and door frame finish with polish, And with brass Hinges and Handle of Enox brand.	L/s	1 Sqft			
					<b>Amount (Rs.)</b>	-
					<b>Add:- GST @ 18%</b>	-
					<b>Total Amount (Rs.)</b>	-

All the terms and conditions given in notifications Should be studied thoroughly and accepted fully.

Thanking you,

Yours truly,

Name of the Company  
Signature of the Proprietor  
Date :

Note : Please enclose 1. Self attested GST number copy ,  
2. Self attested PAN number copy,  
3. Declaration on the company letter head if GST is not applicable.