



SNDT WOMEN'S UNIVERSITY
1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

Estate Dept./2019-20/ (Not. 3)/43

July 10, 2019


Sub: Quotation of Repairing work of Staircase area from ground floor to terrace level in Analytical Chemistry lab, at SNDT Women's University, Juhu Campus.

Madam/Sir,

Sealed quotations are invited for repairing work of Staircase area from ground floor to terrace level in Analytical Chemistry lab, at SNDT Women's University, Juhu Campus. Interested vendors are to be submit their quote in the format given as Annexure A on company letter head. Quotation should be submitted to The Office of The Registrar at Churchgate campus on or before 22Nd July 2019.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

(Dr. Deepak Deshpande)
Registrar



SNDT WOMEN'S UNIVERSITY
1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

(Offer should filled on letter head)

Annexure A

To,
The Registrar
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for Repairing work of Staircase area from ground floor to terrace level in Analytical Chemistry lab at SNDT Women's University, Juhu Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No	Description	Qty	Unit	Rate	Amount
1	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 meters or spreading in the compound and cleaning the site etc. complete.	125.00	Sqmt.		
2	Breaking/Chipping carefully the loose concrete/plaster of distressed member without damaging existing strong concrete by means of sharp chissle which should tempered regularly or high frequency low impact hammers used, cleaning the surface by water jet pressure pump at 4 to 5 kg/sqcm pressure to remove chlorides and loose particles, air drying the surface etc, The work should be carried out with all the safety measures like helmet, safety belt and adequate labour insurance under the supervision of qualified supervisor. (The damaged area of member/concrete will be measured) etc complete. (Excluding all taxes)	10.00	Sqmt.		
3	Providing and applying of bond coat approved epoxy resin MasterBrase 1414 of BASF/EPI Bond of Krishna CONchem/or equivalent before polymer plaster/concrete to have the perfect bond between old concrete and new concrete/polymer plaster surface within half an hour of after application of bond coat conforming to ASTM C 881 Type 2, using nylon scaffolding labour etc complete. (Excluding all taxes)	10.00	Sqmt.		



SNDT WOMEN'S UNIVERSITY

1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

Sr. No	Description	Qty	Unit	Rate	Amount
4	Providing and applying 30mm thick polymer mortar to load carrying R.C.C. Member in two layers in proportion of 1:5:15 by weight of high dispersion polymer having solid content 37% +1% MasterEmaco SBR 2 of BASF/FOSROC/Krishna Conchem or equivalent approved make and quality, cement ratio for desired consistency and applying and finishing by floating, after curing initial setting time applying bonding coat for 2 nd coat etc. as per manufactures specifications etc complete. (Excluding all taxes)	10.00	Sqmt.		
5	Providing internal cement plaster 25mm thick in two coats in cement mortar 1:4 without neeru finish, to concrete, brick or stone surfaces, in all positions including scaffolding and curing etc. complete.	70.00	Sqmt.		
6	Providing and applying Two coats of wall care Putty of 2mm thickness for plastered surface and 5-6mm thickness finished concrete surface to Ceiling and Walls to prepare surface even and smooth of Brands BIRLA WHITE, BERGER, BISION, J.K., make, etc complete. a) For plastered walls/ceiling 2mm	70.00	Sqmt.		
7	Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.	130.00	Sqmt.		
8	Providing and applying plastic emulsion paint of approved quality, colour and shade to new surface in three coats including scaffolding, preparing the surface. (excluding primer coat) etc. complete.	100.00	Sqmt.		
9	Scrapping the old plastered internal surface with sand paper and coating the entire surface with mixture of whiting or glue and linseed on including scaffolding etc complete as directed.	100.00	Sqmt.		
10	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat	55.00	Sqmt.		



SNDT WOMEN'S UNIVERSITY

1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

Sr. No	Description	Qty	Unit	Rate	Amount
	thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc. complete.				
11	Providing and applying two coats of exterior acrylic emulsion paint confirming to corresponding I.S. of approved manufacture and of approved colour to the plastered surfaces including cleaning, preparing the plaster surface, applying primer coat, scaffolding if necessary, and watering the surface for two days etc complete.	55.00	Sqmt.		
12	Providing and laying machine cut machine polished machine cut Kota stone slabs 20 to 25 mm thick for treads and risers of steps and staircases, with rounded nosing for the treads on a bed of 1:4 cement mortar including cement float, filling joints with neat cement slurry, curing, polishing and cleaning etc. complete.	7.00	Sqmt.		
13	Providing and fixing in position anodized extruded aluminum door with fully aluminum composite panel having frame made out of extruded tubular section of size 50mm x 25mm with 4mm thick with aluminum composite panel fixed with P.V.C. cushioning beading as per approved drawing etc complete.	4.00	Sqmt.		
14	Lowering down the debris obtained from breaking and removing the cement plaster/burnt brick masonry of the first floor by any means without causing dust nuisance and damage to structure, stacking the same as and where directed including cleaning the site complete. (Rate for loose material)	12.00	Cum.		
15	Removing any kind of debris including loading in truck and conveying to approved dumping point beyond MCGM limits, unloading, spreading etc complete.	12.00	Cum.		
16	Removing G.I. or A.C. sheet roofing including purlins, principal rafters etc. including sorting serviceable and unserviceable materials, stacking the same as and where directed in the compound including scaffolding etc. complete.	30.00	Sqmt.		
17	Providing and fixing 6.00 mm thick ISI mark Asbestos Cement Corrugated sheet roofing including	30.00	Sqmt.		



SNDT WOMEN'S UNIVERSITY
1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

Sr. No	Description	Qty	Unit	Rate	Amount
	galvanized iron 'J' or 'L' hook bolts galvanized iron band bituminous G.I. washers, galvanized iron clamps, bolts, nuts and scaffolding etc. complete.				
18	Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/ granite/quartzite/gneiss metal for steps including steel centering, plywood/steel formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V.S.I. quality Artificial Sand	1.500	Cubic Meter		
	Total Amount				

All the terms and conditions given in notifications are studied thoroughly and accepted fully.

Thanking You,

Yours Faithfully,

Name of Company

Signature of the Proprietor

Date:

Note: Enclose GST number, PAN number, declaration if GST is not applicable.