

SNDT Women's University
1, Nathibal Thackersey Road,
Mumbai 400 020
Phone: +91 22 2203 1879
Fax: +91 22 2201 8228



सीमली ना. दा. डाकरडी विद्यापीठ
१, नाथीबाई ठाकरसी मार्ग
मुंबई ४०० ०२०
Telegram: UNIWOMEN
Website: sndt.ac.in

Estate Dept./2020-21 /(Not.7)/166

March 25, 2021

Sub: Quotation for Laying RCC Pipe for storm water drain line at road crossing area, at SNDT Women's University Pune Campus.

Madam/Sir,

Sealed quotations are invited for Laying RCC Pipe for storm water drain line at road crossing area, at SNDT Women's University Pune Campus. . Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the Office of "The Registrar" at Churchgate campus on or before 03rd April 2021 Contractor should submit their.

- i) GST No.
- ii) PAN no.
- iii) Client List,
- iv) Company profile,
- v) Last 3 years audited profit lost statement along with Quotation

Quotation should be submitted in closed envelop and on top write the subject.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

MKS
25/03/2021
**(Dr. Meena Kute)
Registrar(Addl.Charge)**

SNDT Women's University
1, Nathibal Thackersey Road,
Mumbai 400 020
Phone: +91 22 2203 1879
Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ
१, नाथीबाई ठाकरसी मार्ग
मुंबई ४०० ०२०
Telegram: UNIWOMEN
Website: sndt.ac.in

(Offer should filled on letter head)

Annexure A

To,
The Registrar
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation Provision for Laying RCC Pipe for storm water drain line at road crossing area, at SNDT Women's University Pune Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description of Item	Qty	Unit	Rate	Amount
01	Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m) By Manual Means	90.00	Cum.		
02	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for steps including steel centering, plywood/steel formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.),with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V.S.I. quality Artificial Sand	10.500	Cum.		

SNDT Women's University

1, Nathibal Thackersey Road,

Mumbai -100 020

Phone: +91 22 2203 1879

Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ

१, नाथीबाई ठाकरसी मार्ग

मुंबई ४०० ०२०

Telegram: UNIWOMEN

Website: sndt.ac.in

03	Providing and laying cement concrete pipe of IS 458:2003 NP-2 class of 450mm diameter in proper line, level and slope including providing and fixing collars in cement mortar 1:2 and curing etc. complete.	40.00	Rmt.		
04	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually , striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete.	13.500	Cum.		
05	Providing rough cast cement plaster externally in two coats with coloured cement finish to concrete/ brick/ stone masonry surfaces in all positions with base coat 12 to 15 mm. thick in C.M. 1:4 using gray cement and rough cast treatment 12 mm thick in proportion of 1:1 1/2:3 using colour pigment including scaffolding and fourteen days curing etc. complete.	60.00	Sqm.		
06	Site cleaning work as per instruction	1.00	Job		
	Total				

All the terms and conditions given in notifications are studied thoroughly and accepted fully.

Thanking You,

Yours Faithfully,

Name of Company

Signature of the Proprietor

Date:

Note: Enclose GST number, PAN number, declaration if GST is not applicable