

SNDT Women's University

1, Nathibai Thackersey Road,
Mumbai 400 020
Phone: +91 22 2203 1879
Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ
१, नाथीबाई ठाकरसी मार्ग
मुंबई ४०० ०२०
Telegram: UNIWOMEN
Website: sndt.ac.in

Estate Section/2024-25/41

May 02nd, 2024

SUB: Quotation for Repairing to plastering and rain water pipe & external wall painting work of new home science building at SNDTWU, Pune Campus.

Madam/Sir,

Sealed quotations are invited for Quotation for Painting work to Repairing to plastering and rain water pipe & external wall painting work of new home science building at SNDTWU, Pune Campus. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before **10th May 2024**. Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop. Envelop may contains following documents in respective envelop:

A) Technical Bid

- i. Profile of the vendor
- ii. Work Experience Certificate from the concerned the organization where work has been executed.
- iii. GST Certificate
- iv. PAN Copy
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant

B) Financial Bid

- vii. Mentioning including all taxes
- viii. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Regards,

Prof. Vilas D. Nandavadekar

(Offer should filled on letter head)
Annexure A

To,

The Registrar,
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for Repairing to plastering and rain water pipe & external wall painting work of new home science building at SNDTWU, Pune Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description of work	Qty.	Unit	Rate	Amount
1	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete.	94.00	Sqm.		
2	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 1.5 mm thick in cement mortar 1:4 using waterproofing compound at 1Kilogramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.	94.00	Sqm.		
3	Scrapping the old plastered including scaffolding and preparing the old surface etc. Complete as directed	1510.00	Sqm.		
4	Providing and applying two coats of exterior weather shield paint of approved manufacture and of approved colour to the plastered surface including cleaning preparing the plaster surface applying primer coats scaffolding if necessary and watering the surface for two days etc.complete.	1510.00	Sqm.		
5	Removing iron or iron or wrought iron or A.C. pipe and stacking them as directed wih all leads, lift etc.complete.	127.00	Rm.		

6	Providing and fixing P.V.C. Rain water pipes of 110 mm outlet diameter and having wall thickness of 2.2 to 2.7 mm confiring to I.S. 13592-1992 including proper rainwater receiving recess with P.V.C. plug bend necessary fitting such as off sets, shoes, including fixing the pipe on wall using approval wooden cleats projecting 25 mm to 110mm from faced wall a fixing with clips of approved quality and one number filling the joints using rubber gasket with solvent cement and properly resting the shoe of pipes on c.c. or masonnnnnnry blocks including necessary scaffolding and maintenance for 3 yrs for any leakages or dislocations of pipes. Al the P.V.C. fitting and additional 2 piece socket clips shall be got approved from engineeor in charges etc.complete.	127.00	Rm.		
	Total				
	Taxes will be paid at actual at the prevailing time.				
	Net Total				

