

SNDT Women's University

1, Nathibai Thackersey Road,
Mumbai 400 020
Phone: +91 22 2203 1879
Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ
१, नाथीबाई ठाकरसी मार्ग
मुंबई ४०० ०२०
Telegram: UNIWOMEN
Website: sndt.ac.in

Estate Section/2024-25/194

October 05th, 2024

SUB: Quotation for Refurbishment of P.A. office of Statutory officers at ground floor in Main bldg. S.N.D.T.W.U. Churchgate Campus.

Madam/Sir,

Sealed quotations are invited for Quotation for Refurbishment of P.A. office of Statutory officers at ground floor in Main bldg. S.N.D.T.W.U. Churchgate Campus. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before 16 October 2024 Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop.

Envelop may contains following documents in respective envelop:

A) Technical Bid

- i. Profile of the vendor
- ii. Work Experience Certificate from the concerned the organization where work has been executed.
- iii. GST Certificate
- iv. PAN Copy
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant

B) Financial Bid

- vii. Mentioning including all taxes
- viii. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Regards,

Prof. Vilas D. Nandavadekar

Registrar
SNDT Women's University
Mumbai - 20

1

(Offer should filled on letter head)
Annexure A

To,

The Registrar,
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for Refurbishment of P.A. office of Statutory officers at ground floor in Main bldg. S.N.D.T.W.U. Churchgate Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description of work	Qty.	Unit	Rate	Amount
1	Removing loose rust from the reinforcement bars by wire brushing, light hammering etc. and applying sulphate and chloride free inorganic single component rust remover Rusticide as approved by Engineer in charge conforming to IS 9077. The rusted surface shall become blackish non rusted colour. After 24 hours of application of rust remover, loose particles shall be removed by brush. Apply one more coat of Rusticide. Apply bonding coat slurry of high performance acrylic polymer - Methyl 2-methylpropenoate copolymer with another enoate as approved by Engineer in charge on entire surface. Mix 1 Kg of acrylic polymer with 0.5 Kg of cement. Finish it with ready to use repair polymer modified mortar based on special cements, aldehyde based polymers with thixotropy modifying agents as approved by Engineer in charge (The Polymer Modified Mortar (PMM) should attain min. compressive strength of 20 N/mm ² in 1 day and 30 N/mm ² in 7 days) by adding 13 - 16% water by weight of polymer modified mortar for treatment to the damaged RCC members. Add 1 Kg of Migrating Corrosion Inhibiting Admixture as approved by Engineer in charge per 25 Kg bag of polymer modified mortar.	13.00	Sqm		

	After mixing polymer modified mortar, it can be trowel applied or sprayed. When applying by hand, polymer modified mortar must be forced tightly into the substrate to ensure complete contact with the substrate. (If scaffolding is required, same shall be provided and will be paid under relevant item) (Upto 15 mm thickness at a time).			
2	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete.	15	Sqm.	
3	Providing internal cement plaster 6 mm thick in a single coat in cement mortar 1:4 without neeru finish to concrete surface in all positions including scaffolding and curing etc. complete.	13.00	Sqm.	
4	Providing internal cement plaster 20mm thick in Single coats in cement mortar 1:5 without neeru finish, to concrete, brick surface, in all positions including scaffolding and curing etc. complete	2.00	Sqm.	
5	Providing and applying Royale Luxury Emulsion of approved make on internal wall surface as detailed below Scrapping for surface with emery paper and wipe clean for area. wall primer with brush by adding mineral turpentine oil by 8 to 10 % or water by 15 to 20% allowing to dry for 6 to 8 hoursAfter applying acrylic wall putty with appropriate prpportion of water of allow to dry for period of 4 to 6 hours of activity. Scrapping with emery paper and wipe clean Applying paints Royale Luxury emulsion 1st coat with brush water content water 40 to 45% or 65 to 70% by role Applying paints Royale luxury emulsion 2nd coat with brush with water content 40 to 45% or 65 to 70 % by roller. (With prior approval of S.E.)	95.00	Sqm.	
6	Providing and applying two coats of flat oil paint of approved colour to the old structural steel work and iron work previously painted in building including scaffolding, if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete.	20.00	Sqm.	
7	Providing and applying priming coat over new wood and wood based surfaces, including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter, sand papering and knotting, scaffolding etc. complete.	20.00	Sqm.	

8	Providing and fixing on site notice board made out of 6 mm marine ply of the requisite manufacture generally confirming to I.S.310/I.S.710-1980 backing and 12 mm thick soft board covered with tapestry/up to Rs. 200 per meter including necessary lipping (BTC), moulding, hardware, polishing etc. and Anti-termite treatment to plywood and woodwork with ten years guarantee bond etc. including all leads & lifts etc. complete as per Architect Drawing and instructions of Engineer in Charge.	5.20	Sqm.		
9	Providing & fixing different size of table made out of 19 mm thick plywood of the requisite manufacture i.e. Anchor/Century/Kenwood/Greenply for equivalent generally confirming to I.S. 710-1980 for Top, Vertical side and 6 mm & 12 mm thick plywood for back & drawer with necessary B.T.C wood lipping & moduling. The External shall be finished with 3.5 to 4 mm thick greenply Veneer (Wood Crrests) Sheet OR laminate sheet Excluding melamine polish and internal shall be finished laminate 0.80 mm thick (Royale touch) etc. Complete as per instructions of Engineer-in-charge.	8.67	Sqm.		
10	Providing and fixing glass partition of 12mm thick toughened glass with etching pattern with necessary fittings, and araldite & fixtures etc. Complete as per drawing and instruction of Engineer in charge.	0.98	Sqm.		
11	Providing and fixing wooden partition at require location having height more than 1.34m and minimum 65mm thick made by using 50 X 50mm (finish size) CPTW section framing at 600mm centre, covered with 6mm to 9mm ply of the requisite manufacture viz. Anchor/Century /Kenwood/ Duro/jet or equivalent generally confirming to I.S. 303/I.S.70-1980 on both side. The partition shall be finished with formica laminate sheet finished lamination pattern with or without grooves and externally with 8mm thick glass necessary lipping (B7C), moulding, antitermite treatment to plywood and woodwork including all leads & lifts etc. Complete as per Architect's Drawing and instruction of Engineer In Charge	8.92	Sqm.		
12	Providing and fixing Cupboard type Sto. age Unit made out of 19mm thick plywood of the requisite manufacture generally confirming to I.S. 710-1980 for frames, internal verticals horizontal divisions, shutters and 6mm & 12mm thick plywood for	9.76	Sqm.		

	drawers with locks, handles, hardware, lipping & beading patti (BTC) etc. Etc. Complete as per drawing and instruction of Engineer-in-charge etc. Complete.				
13	Fixing of existing storage after refurbishment work of storage by replacing laminate fixtures etc complete as directed by Engineer In Charge.	4.88	Sqm.		
14	Supplying Carpenter I Class Skilled for removing existing partition and storage and stacking the same as and where directed including the site complete	10.00	Day		
15	Providing and fixing 2.0mm thick polyvenyl vinyl chloride flooring including leveling the base with white cement including pasting with appropriate material cleaning the surface etc. Complete.	26.00	Sqm.		
16	Making and providing by fixing roller blinds fabricks curtains for window in approved sample by using powder coated rod and machinical system with chain for opening / closing moments of the blinds and fixing properly at sites and at director Engineer in charge.	6.50	Sqm.		
	Total				
	Taxes will be paid at actual at the prevailing time.				
	Net Total				

