

## SNDT Women's University

1, Nathibai Thackersey Road,  
Mumbai 400 020  
Phone: +91 22 2203 1879  
Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ

१, नाथीबाई ठाकरसी मार्ग

मुंबई ४०० ०२०

Telegram: UNIWOMEN

Website: sndt.ac.in

Estate Section/2025-26/62

June 02<sup>nd</sup>, 2025

### SUB:Quotation for Construction of pump room at S.N.D.T. Women's University Pune Campus.

Madam/Sir,

Sealed quotations are invited for Quotation for Construction of pump room at S.N.D.T. Women's University Pune Campus. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before **10<sup>th</sup> June 2025** Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop.

Envelop may contains following documents in respective envelop:

#### A) Technical Bid

- i. Profile of the vendor
- ii. Work Experience Certificate from the concerned the organization where work has been executed.
- iii. GST Certificate
- iv. PAN Copy
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant

#### B) Financial Bid

- vii. Mentioning including all taxes
- viii. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

**The University reserves the right to reject any or all quotations without assigning any reasons thereof.**

*[Handwritten signature]*  
2/6

Shri. Rakesh Valvi

Registrar (Addl. Charge)

**(Offer should filled on letter head)**  
**Annexure A**

To,

The Registrar,  
SNDT Women's University,  
Churchgate, Mumbai

**SUB:Quotation for Construction of pump room at S.N.D.T. Women's University Pune Campus.**

**Respected Madam/Sir,**

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description of work	Qty.	Unit	Rate	Amount
1	Dismantling brick masonry in lime or cement mortar and stacking the materils as directed with all leads, lifts etc.	11.00	Cum		
2	Removing G.I. or A.C. sheet roofing including purlins, principal rafters etc. including sorting serviceable and unserviceable materials, stacking the same as and where directed in the compound including scaffolding etc. complete.	20.00	Sqm.		
3	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 0.00 to 1.50 m.) By Manual Means	7.00	Cum		
4	Providing and laying Cast in situ/Ready Mixcement concrete in M20 of trap/granite/quartzite/gneiss metal for steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	5.00	Cum		
5	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm	10.00	Cum		



	including watering and compaction etc. complete.				
6	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.	4.00	Cum		
7	Providing uncaused rubble masonry of trap / granite / quartzite / gneiss stones in cement mortar 1:6 in foundation and plinth of inner walls / in plinth of external walls including bailing out water manually , striking joints on un exposed faces and watering etc.complete.	7.00	Cum		
8	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually , striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete.	12.00	Cum		
9	Providing rough cast cement plaster externally in two coats to concrete, brick or stone masonry surfaces in all positions with base coat of 12 to 15 mm thick in C.M. 1:4 and rough cast treatment 12mm thick in proportion 1:1 1/2:3 including scaffolding and fourteen days curing complete.	64.00	Sqm		
10	Providing and fixing solid core flush door shutter commercial in single leaf 32 mm thick without ventilator commercial type of exterior grade as per detailed drawings with wrought iron hold fast, stainless steel fixtures and fastenings and handles on both sides and finishing with oil painting 3 coats complete.	2.00	Sqm		
11	Providing and fixing steel window of various sizes as per detailed drawing without hot dip zinc coating, without ventilators, including fabricating / glazing with plain / obscured glass panels of approved type and quality, iron oxidised fixtures and fastenings, finishing with oil painting two coats complete (with guard bars 12 mm square at 10 cm c/c.)	2.00	Sqm		
12	Providing structural steel work of rectangular hollow steel section for steel trusses, other similar trussed items like purlin and members with all bracing, gusset plates etc. as per detailed designs and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted/bolted/ welded connections and one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade complete.	0.90	Metric Tonnes		
13	Providing and fixing corrugated galvanised iron sheets of 0.63mm thick (24 B.W.G.) for roofing without wind tiles including fastening with galvanised iron screws and bolts, lead and bitumen washers as per drawing etc.	20.00	Sqm		

	complete.(Weight of 5.5 Kilogram/sq.m.).				
14	Providing and applying two coats of exterior acrylic emulsion paint confirming to corresponding I.S. of approved manufacture and of approved colour to the plastered surfaces including cleaning ,preparing the plaster surface, applying primer coat ,scaffolding if necessary , and watering the surface for two days etc complete.	105.00	Sqm		
15	Providing and laying Polished Tandur Stone flooring 25mm to 30mm thick required width in plain/ diamond pattern on a bed of 1:6 C.M. including cement float, filling joints with neat cement slurry, curing, polishing and cleaning etc. complete.	25.00	Sqm		
	Total				
	Taxes will be paid at actual at the prevailing time.				
	Net Total				