


SNDT Women's University

1, Nathibai Thackersey Road,

Mumbai 400 020

Phone: +91 22 2203 1879

Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ

१, नाथीबाई ठाकरसी मार्ग

मुंबई ४०० ०२०

Telegram: UNIWOMEN

Website: sndt.ac.in

Estate Section/2024-25/325

January 14th, 2025

SUB: Quotation for Construction of Abhivyakti Katta at S.N.D.T. Women's University, Juhu Campus.

Madam/Sir,

Sealed quotations are invited for Quotation for Construction of Abhivyakti Katta at S.N.D.T. Women's University, Juhu Campus. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before **03rd February 2025** Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop.

Envelop may contains following documents in respective envelop:

A) Technical Bid

- i. Profile of the vendor
- ii. Work Experience Certificate from the concerned the organization where work has been executed.
- iii. GST Certificate
- iv. PAN Copy
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant

B) Financial Bid

- vii. Mentioning including all taxes
- viii. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Regards,

Prof. Vilas D. Nandavadekar

02/11/25

Registrar

SNDT Women's University

Mumbai - 20.

(Offer should filled on letter head)

Annexure A

To,

The Registrar,
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for Construction of Abhivyakti Katta at S.N.D.T. Women's University, Juhu Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

| Sr. No. | Description of work | Qty. | Unit | Rate | Amount |
|---------|--|-------|------|------|--------|
| 1 | Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually , striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete. | 44.00 | Cum. | | |
| 2 | Providing and fixing machine cut machine polished 18 mm to 20 mm thick telephone black / Amba White / Cat bary brown / RBI red / Ocean Brown granite stone for treads and risers of steps and staircases of approved colour and shade with full moulding and three grooved line for the treads on bed of 1:4 Cement mortar including float filling joints with neat cement slurry curing polishing and cleaning etc. complete. | 44.26 | Sqm. | | |
| 3 | Providing rough cast cement plaster externally in two coats to concrete, brick or stone masonry surfaces in all positions with base coat of 12 to 15 mm thick in C.M. 1:4 and rough cast treatment 12mm thick in proportion 1:1 1/2:3 including scaffolding and fourteen days curing complete. | 48.44 | Sqm. | | |
| 4 | Providing and applying two coats Apex Ultima Puranature Anti-Pollution Or equivalent approved brand, paint should decomposes organic | 15.00 | Sqm. | | |

| | | | | | |
|---|--|--------|------|--|--|
| | substances and inorganic gases(NOx, VOC's, CO, SOx, formaldehydes, etc.) in presence of natural or artificial light. It contains Graphene and nanoparticles of titanium oxide. and Absorbs CO2 (4.8 Kilogram/15 l). plaster crack should be filled by Acrylic base Crack seal/Textured Crack filler, Paint has to applied on one coat of Apex Ultima Puranature Anti-Pollution Primer or Equivalent. Warranty Should be given by the Manufaturer The work should be done by the Manufacturer Recommended applicator and he should be able to furnish stage wise onsite technical reports from the concerned company technologist. | | | | |
| 5 | Providing and laying Cast in situ/Ready Mix cement concrete M-30 of trap / granite/quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. columns as per detailed designs and drawing or as directed including Steel centering formwork, cover blocks laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel). with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) | 14.040 | Cum. | | |
| 6 | Providing and applying Texture plaster with finishing with texture material of approved make in 3 to 4 millimeter thickness on previously plastered surface, including Plaster Groove 6mm thickness or Tape Grooves 35 to 45 mm thickness or as required, in all position including preparing the surface, scaffolding etc. complete. | 22.24 | Sqm. | | |
| 7 | Providing and fixing mild steel grill gate as per the detailed drawing including hinges, locking arrangements and painting in three coats of oil paint of approved colour and shade etc. complete.(weight 18 Kilogram. to 20 Kilogram. Per Sq.m.) Spec.One Number: As directed by Engineer- in-charge. | 12.00 | Sqm. | | |
| 8 | Finishing upto 225 mm thick cement concrete laid to proper level and slope including compacting finishing with tremix treatment for paving slab with compaction by screed vibrator , removing | 25.00 | Sqm. | | |

| | | | | |
|---|---|-------|------|--|
| | excess water from the cement concrete by tremix vacuum dewatering system , finishing the surface with floater and trowel including all etc. complete as directed | | | |
| 9 | Providing, applying and finishing the top surface of concrete with stamp/stencil of approved pattern and colour, in accordance with manufacturer's specification of any approved brand of colour hardener @ of 3.5 kgs/m ² ; including floating of colour hardened over concrete surface with different types of floaters; including application of release agent (@) of 0.15 k ys m ² , stamping over the concrete surface with stamping tools: including cleaning of surface with water and cutting of finished concrete; includ ng application of two coats of acrylic based sealer for finishing. Colour hardener and release agent shall be tested for abrasion resistance for a depth of wear, should not be more than 0.025 mm. Coverage of sealer should not be more than 6.5 sq.m per one litre coat; including cost of skilled manpower, cutting machine, sprayer and all tools tackles for all activities; complete smooth & Tinish as per direction of Engineer-In-Charge | 25.00 | Sqm. | |
| | Total | | | |
| | Taxes will be paid at actual at the prevailing time. | | | |
| | Net Total | | | |