

SNDT Women's University

3, Nathibai Thackersey Road,
Mumbai 400 020
Phone: +91 22 2203 1879
Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ
१, नाथीबाई ठाकरसी मार्ग
मुंबई ४०० ०२०
Telegram: UNIWOMEN
Website: sndt.ac.in

Estate Section/2024-25/348

February 04th, 2025

SUB: Quotation for Repair to internal painting & plastering work of New Home Science building at SNDTWU Pune Campus.

Madam/Sir,

Sealed quotations are invited for Quotation for Repair to internal painting & plastering work of New Home Science building at SNDTWU Pune Campus. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before **11 February 2025**. Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop.

Envelop may contains following documents in respective envelop:

A) Technical Bid

- i. Profile of the vendor
- ii. Work Experience Certificate from the concerned the organization where work has been executed.
- iii. GST Certificate
- iv. PAN Copy
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant

B) Financial Bid

- vii. Mentioning including all taxes
- viii. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Regards,

Prof. Vilas D. Nandavadekar

Registrar
SNDT Women's University
Mumbai - 20

(Offer should filled on letter head)
Annexure A

To,

The Registrar,
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for Repair to internal painting & plastering work of New Home Science building at SNDTWU Pune Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description of work	Qty.	Unit	Rate	Amount
1	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. Complete	119.00	Sqm.		
2	Scrapping the old plastered internal surface with sand paper and coating the entire surface with mixture of whiting or glue and linseed oil including scaffolding etc. Complete as directed.	2753.00	Sqm.		
3	Providing and applying plaster 20 mm thick in cement motar 1:3 with neat finishing, floating using waterproofing compound at compound at the rate of 1 kg per bag of cement of approved make including scaffolding and query etc.completed.	119.00	Sqm.		
4	Providing and applying priming coat over new/old steel and other metal surfaces including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and scoured with wire brushes, fine steel wool, scrappers and sand paper, scaffolding etc. Complete.	630.00	Sqm.		
5	Providing and applying Royale Luxury Emulsion of approved make on internal wall surface as detailed below,scrapping for surface with emery paper and wipe clean for area. Wall primer with brush by adding mineral turpentine oil by 8 to 10% or water	2122.00	Sqm.		

	by 15 to 20% allowing to dry for 6 to 8 hours After applying acrylic wall putty with appropriate proportion of water of allow to dry for period of 4 to 6 hours of activity. Scrapping with emery paper and wipe clean Applying paints Royale Luxury emulsion 1st coat with brush water content water 40 to 45% or 655 to 70% by the Applying paints Royale luxury emulsion 2nd coat with brush with water content 40 to 45% or 65 to 70% by roller. (With prior approval of S.E.)				
6	Providing and applying two coats of synthetic enamel paint of approved colour to new/old structural steel work and wood work in building, including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc complete.	630.00	Sqm.		
	Total				
	Taxes will be paid at actual at the prevailing time.				
	Net Total				

