

SNDT Women's University

1, Nathibai Thackersey Road,

Mumbai 400 020

Phone: +91 22 2203 1879

Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ

१, नाथीबाई ठाकरसी मार्ग

मुंबई ४०० ०२०

Telegram: UNIWOMEN

Website: sndt.ac.in

Estate Section/2024-25/363

February 13th, 2025

SUB: Quotation for Construction of Abhivyakti Katta for Student at S. N. D. T. Women's University, Pune Campus.

Madam/Sir,

Sealed quotations are invited for Quotation for Construction of Abhivyakti Katta for Student at S. N. D. T. Women's University, Pune Campus. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before 21st February, 2024. Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop.

Envelop may contains following documents in respective envelop:

A) Technical Bid

- i. Profile of the vendor
- ii. Work Experience Certificate from the concerned the organization where work has been executed.
- iii. GST Certificate
- iv. PAN Copy
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant

B) Financial Bid

- vii. Mentioning including all taxes
- viii. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Regards,

Prof. Vilas D. Nandavadekar

(Offer should filled on letter head)
Annexure A

To,

The Registrar,
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for Construction of Abhivyakti Katta for Student at S. N. D. T. Women's University, Pune Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description of work	Qty.	Unit	Rate	Amount
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 0.00 to 1.50 m.) By Manual Means	23.00	Cum		
2	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete.	25.00	Cum		
3	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.	14.00	Cum		
4	Providing and laying Cast in situ/Ready Mixcement concrete in M20 of trap/ granite/quartzite/gneiss metal for steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for	17.00	Cum		

	rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)				
5	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually , striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete.	46.00	Cum		
6	Providing rough cast cement plaster externally in two coats to concrete, brick or stone masonry surfaces in all positions with base coat of 12 to 15 mm thick in C.M. 1:4 and rough cast treatment 12mm thick in proportion 1:1 1/2:3 including scaffolding and fourteen days curing complete.	67.00	Cum		
7	Providing and laying in position flooring of telephone black/Amba White/Cat bary brown/Ruby red/Ocean Brown granite stone of approved shade and size 18 mm to 20 mm thick on bedd 1:6 cement mortar including cement floats sriking joints, pointing in C.M. 1:3 curing and cleaning etc.complete	46.00	Sqm		
8	Providing and applying two coats of exterior acrylic emulsion/Apex Ultima paint confirming to corresponding I.S. of approved manufacture and of approved colour to the plastered surfaces including cleaning, preparing the plaster surface ,applying primer coat, scaffolding if necessary, and watering the surface for two days etc. complete.	29.00	Sqm		
9	Providing and applying Texture plaster with finishing with texture internal plaster with finishing with texture material of approve make in 3 to 4 millimeter thickness previously plastered surface, including plaster froov-6 mm thickness or Tape Grooves 3 to 4 thickness or as required, I at position including preparing the surface, scaffolding etc.complete.	24.00	Sqm		
10	Providing and fixing M.S.grill gate as per detailed drawing including locking arrangement and painting in three coats of oil paint of approved coloured and shade etc.complete (weight 18 kg to 20 kg.per sq.m.)	12.00	Sqm		
11	Providing and fixing heaby duty inter locking concrete coloured pavin blocks of 60 mm	25.00	Sqm		

	thickness/ a of having a strength of 300 kg/51 cm a approved quality and shap on a bed of crushed sand of 25 to 30 mm thick including skirting joints and cleaning etc.complete.				
12	Finishing upto 225 mm thick cement concrete laid to proper level and slope including compacting finishing with tremix treatment for paving slab with compaction by screed vibrator, removing excess water from the cement concrete by tremix vacuum dewatering system, finishing the surface with floater and trowel including all etc.complete as directed.	31.00	Sqm		
	Total				
	Taxes will be paid at actual at the prevailing time.				
	Net Total				