SNDT Women's University

1, Nathibai Thackersey Road, Mumbai 400 020

Phone:

+91 22 2203 1879 +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ

१, नाथीबाई ठाकरसी मार्ग

मुंबई ४०० ०२०

Telegram: UNIWOMEN Website: sndt.ac.in

Septemberay 20th, 2025

Estate Section/2025-26/191

SUB: Quotation for Refurbishment of proposed KIOSK at SNDT Women's University, Churchate Campus.

Madam/Sir,

Sealed quotations are invited for Quotation for "Refurbishment of proposed KIOSK at SNDT Women's University, Churchate Campus." Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before 30 5 september 25 Contractor should submit their quotes in two envelopes enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop.

Envelop may contains following documents in respective envelop:

A) Technical Bid

- Profile of the vendor i.
- Work Experience Certificate from the concerned the organization where ii. work has been executed.
- iii. **GST** Certificate
- **PAN Copy** iv.
- If GST is not applicable then declaration of the same. v.
- If GST is applicable, then No Dues Certificate authorized by a Chartered vi. Accountant

B) Financial Bid

- Mentioning including all taxes vii.
- If required work is mentioned component wise then the amount is to be given viii. component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Regards,

andavadekar Prof. Vilas D. N Women's University

Mumbai - 20

(Offer should filled on letter head) Annexure A

To,

The Registrar, SNDT Women's University, Churchgate, Mumbai

Sub: Quotation for Refurbishment of proposed KIOSK at SNDT Women's University, Churchgate Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate

possible as below:

| Sr. No. | Description of work | Qty. | Unit | Rate | Amount |
|------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|------|--------|
| 1 | Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete | 0.95 | Cum | | |
| 2 | Providing rough cast cement plaster externally in two coats to concrete, brick or stone masonry surfaces in all positions with base coat of 12 to 15 mm thick in C.M. 1:4 and rough cast treatment 12mm thick in proportion 1:1 1/2:3 including scaffolding and fourteen days curing complete. Providing rough cast cement plaster externally in two coats to concrete, brick or stone masonry surfaces in all positions with base coat of 12 to 15 mm thick in C.M. 1:4 and rough cast treatment 12mm thick in proportion 1:1 1/2:3 including scaffolding and fourteen days curing complete. | 12.70 | Sqm | | |
| 3 | Providing and laying ceramic tiles having size 30 cm. x 45 cm. confirming to corresponding I.S. for dado and skirting in required position with readymade adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white/ colour cement slurry cleaning curing etc. complete. | 6.35 | Sqm | | |
| 4 | Providing and fixing in position PVC false ceiling with 8mm th. PVC sheet screwed fixed to the under structure of suspended G.1. Gird constructed and suspended from the main ceiling consisting of ceiling section at maximum center to center distance 600 milimeter perimeter channel intermediate channel st maximum center to center distance 1200 milimeter galvanised grid should he fixed to reinforced | 15.70 | Sqm | | |

| | No other Mission | | | |
|---|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----|--|
| | cement concrete slab. The PVC sheet should be tixied to galvanised iron grid with necessary screws. The rate should include necessary additional ceiling sections and intermediate channels. Additional intermediate channel should be fixed to strap hangers for additional support to prevent strapping at every 1200 milimeter item to be completed in all respect including necessary sleeves for ducts fixing of joints cnt outs etc. all complete" | | | |
| 5 | Providing and laying in position flooring of telephone black / Amba White / Cat bary brown / Ruby red / Ocean Brown granite stone of approved shade and size 18 mm to 20 mm thick on bed 1:6 cement mortar including cement floats striking joints, pointing in C.M. 1:3 curing and cleaning etc. complete. | 3.00 | Sqm | |
| 6 | Providing and laying vitrified matt fininsh tiles having size 590 mm to 605 mm x to 605 mm of 8 to 10 mm thickness and confirming IS. 15622-2006 (Group Bla) of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement morar including neat cement float, filling joints, curing and cleaning etc.complete. | 15.70 | Sqm | |
| 7 | Providing and laying vitrified matt finish tiles having size 590 mm to 605 mm x to 605 mm of 8 to 10 mm thickness and confirming IS. 15622-2006 (Group Bla) of approved make, shade and pattern for dado and skirting in required position fixed in 1:4 cement mortar including neat cement float, filling joints, curing and cleaning etc. complete. | 7.54 | Sqm | |
| 8 | Providing and applying Royale Luxury Emulsion of approved make on internal wall surface as detailed below Scrapping for surface with emery paper and wipe clean for area. wall primer with brush by adding mineral turpentine oil by 8 to 10 % or water by 15 to 20% allowing to dry for 6 to 8 hoursAfter applying acrylic wall putty with appropriate preportion of water of allow to dry for period of 4 to 6 hours of activity. Scrapping with emery paper and wipe clean Applying paints Royale Luxury emulsion 1st coat with brush water content water 40 to 45% or 65 to 70% by role Applying paints Royale luxury emulsion 2nd coat with brush with water content 40 to 45% or 65 to 70 % by roller. (With prior approval of S.E.) | 38.76 | Sqm | |
| 9 | Providing and fixing full height partition at require location having height more than 1.34m and minimum 75mm thick made out of 63 x 38 mm thick Aluminium Pipe frame work of size 600 x 600 mm center to center, equivalent with 6 | 9.11 | Sqm | |

| | 4 0 All | | | The state of the s |
|-----|------------------------------------------------------|---------|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | mm to 9mm Alluminium Composite Panel sheet | | | |
| | of the requisite manufacture on both side etc. | | | |
| | complete as per Architect's Drawing and | | | |
| | instruction of Engineer In Charge. | | | |
| | Providing and fixing in position, Single shuttered | | | |
| | aluminium extruded powder coated openable | | | |
| | door of overall size 0.90 m x 2.40 m with | | | |
| | aluminium door frame of powder coated section | | | |
| | 101.60 x 44.75mm , 3.18 mm thick and shutter | | | |
| | comprising of powder coated section having | | | |
| | bottom and lock rail of size 150 mm x 44.5 mm x | | | |
| | 3.00 mm thick top rails 47.62 x 44.45 mm x 3.00 | | | |
| | mm thick , vertical style 47.62 x 44.45 mm,3.00 | | | |
| 10 | | 2.52 | Sqm | |
| 10 | mm thick and for shutter plain glass panes 5 mm | | | |
| | thick for top panels and 12mm thick both side | | | |
| | laminated phenol bonded particle board panels | | | |
| | for bottom panels etc. , I.S.I. mark , with bijagiri | | | |
| | having heavy duty concealed lock, necessary | | | |
| | beading, glazing clips, PVC gaskets, 250mm | | | |
| | length tower bolts, 150mm diam. pad handle, etc. | | | |
| | as per detailed design and drawing or as directed | | | |
| | by engineer in charge including all materials, | | | |
| | labours, and equipment etc. complete | | | |
| | Providing and fixing onsite laminated covering to | | | |
| | column/beam/wall/ slabs by using 19mm th. | | | |
| | Marine ply or the requisite manufacture viz | | | |
| | Anchor/Century/Kenwood/ Duro or equivalent | | | |
| | generally confirming to 1.5.3.)3/1.S.710-1980 | | | |
| | fixed firmly and finished with 1.5 mm thick | | | |
| 11 | laminate (Royale touche) matt/suede/fine line | 4.55 | Sqm | |
| | finished lamination pattern with grooves | | | |
| | externaly incl. Necessary lipping (BTC) moulding, | | | |
| | hardware, polishing etc and Antitermite | | | |
| | | | | |
| | Treatment to Plywood and woodwork including | | | |
| | all leads & lifts etc. Complete as per Architect's | | | |
| | Drawing and Engineer in charge | - Winds | | |
| | Providing and fixing 31mm thick shelf by using | | | |
| | 19mm thick and 12mm thick marine ply or the | | | |
| | requisite manufacture viz | | | |
| | Anchor/Century/Kenwood/ Duro or equivalent | | | |
| | generally confirming to 1.5.3.)3/1.S.710-1980 | | The many | |
| | fixed firmly and finished with 1.5 mm thick | 107 | Sam | |
| 12 | laminate (Royale touche) matt/suede/fine line | 4.87 | Sqm | |
| | finished lamination pattern with grooves | | | |
| | externaly incl. Necessary lipping (BTC) moulding, | | | |
| | hardware, polishing etc and Antitermite | | | |
| | Treatment to Plywood and woodwork including | | | |
| | all leads & lifts etc. Complete as per Architect's | | | |
| | Drawing and Engineer in charge | | | |
| 200 | Low Height Storage - Providing & fixing on site | | 1 | |
| | | | | |
| 12 | 45 cm Deep Low Height Storage Unit at require | 3.77 | Sqm | |
| 13 | location less than 1.35 meter height by using | | | |
| | 19mm marine ply of requisite manufacture | | | |
| | generally confirming to I.S. 303/IS. 710-1980 for | | 1 | |

| | frame 12mm thick maring play for head in | | | |
|----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-----|------|
| | frame, 12mm thick marine ply for back, internal verticals, horizontal divisions with necessary hardware, lipping (BTC), moulding etc. The total shall be finished with formica laminate sheet finished lamination pattern with grooves externally and internally with anti-termite treatement to plywood & wood work including all leads & lifts etc. Complete, as per Architect's Drawing and instruction of Engineer in Charge. | | | |
| 14 | Providing & fixing on site 30cm Deep Over Head Storage Unit at require location less than 1.00 meter height by using 19mm marine ply of requisite manufacture generally confirming to I.S. 303/IS. 710-1980 for frame,, 12mm thick marine ply for back, internal verticals, horizontal divisions with necessary hardware, lipping (BTC), moulding etc. The total shall be finished with formica laminate sheet finished lamination pattern with grooves externally and internally with anti-termite treatement to plywood & wood work including all leads & lifts etc. Complete, as per Architect's Drawing and instruction of Engineer in Charge. | 2.88 | Sqm | |
| 15 | Providing and fixing partition at require location having height more than 1.00 m and minimum 75 mm thick made out of 63 X 38 mm thick Aluminium pipe horizontally.Part of partition shall be provided with 12mm thick toughned glass panel of approved make or as directed, glass fixed with aluminum glass clips and rubber cushioning beading to glass partitions as per approved drawing etc. Complete | 5.95 | Sqm | |
| 16 | P/F in position Different Size of Corian Table made out of 19mm thick marine plywood of the requisite manufacture i.e. Anchor/Century/Kenwood/Greenply or equivalant generally confirming to I S.710-1980 for Top, vertical side and 6mm & 12mm thick marine plywood for back & drawer with necessary B.T.C. wood lipping & moulding. The Table Top shall be finished with Corian sheet 12mm thick and Remaining external sides with 3.5 to 4 mm thick Greenply Veneer (Wood Crrests) sheet Excluding Melamine polish and internal sides shall be finished by laminate sheet 0.80 mm thick (Royale touche) with three years guarantee on requisite stamp paper etc. complete as per drawing and instructions of Engineer - charge | 4.65 | Sqm | |
| | Total Toyac will be said at a facility of the said at a facility of th | | | |
| | Taxes will be paid at actual at the prevailing time. Net Total | | | |
| 1 | ivet ittal | | | |