

# SNDT Women's University

1, Nathibai Thackersey Road,

Mumbai 400 020

Phone: +91 22 2203 1879

Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ

१, नाथीबाई ठाकरसी मार्ग

मुंबई ४०० ०२०

Telegram: UNIWOMEN

Website: sndt.ac.in

Estate Section/2025-26/377

March 05<sup>th</sup>, 2025

**SUB: Quotation for Construction of stage at SNDT Women's University, Pune Campus.**

**Madam/Sir,**

Sealed quotations are invited for Quotation for "Construction of stage at SNDT Women's University, Pune Campus." Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before **09 March 2026**. Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop.

Envelop may contains following documents in respective envelop:

## **A) Technical Bid**

- i. Detailed Company Profile (Contact details of contractor including address, phone number and email ID)
- ii. Copies of Work Completion Certificates / Work Orders for similar works executed in the last three years.
- iii. GST Registration Certificate (Self attested)
- iv. PAN Card (Self attested)
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant
- vii. Income Tax Return or Financial Statement of the last financial year or turnover 1.5 times of the civil work
- viii. Undertaking stating that the contractor has not been blacklisted by any Government / Semi-Government organization.

## **B) Financial Bid**

- I. Mentioning including all taxes
- II. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

**The University reserves the right to reject any or all quotations without assigning any reasons thereof.**

Regards,

Prof. Vilas D. Nandavadekar

**(Offer should filled on letter head)**  
**Annexure A**

To,

The Registrar,  
SNDT Women's University,  
Churchgate, Mumbai

**Sub: Quotation for Construction of stage at SNDT Women's University, Pune Campus.**

**Respected Madam/Sir,**

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description of work	Qty.	Unit	Rate	Amount
1	Excavation for foundation in earth, soils of all types, sand, gravel and soft murum, including removing the excavated material upto a distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift from 1.5m to 3.0m) By Manual Means	70.00	Cu.M		
2	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete.	81.00	Cu.M		
3	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.	27.00	Cu.M		
4	Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/ granite/quartzite/gneiss metal for plain or molded sills, cornice, jambs, block in course, or architraves of required size and shapes including steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.) with fully	21.00	Cu.M		

	automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer etc. complete, With fine aggregate (Crushed sand VSI Grade)				
5	Providing uncaused rubble masonry of trap / granite / quartzite / gneiss stones in cement mortar 1:6 in foundation and plinth of inner walls / in plinth of external walls including bailing out water manually , striking joints on un exposed faces and watering etc.complete.	29.00	Cu.M		
6	Providing tuck pointing with cement mortar 1:3 for stone/Brick masonry including scaffolding and curing etc. complete.	96.00	Sqm		
7	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually , striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete.	9.00	Cu.M		
8	Providing rough cast cement plaster externally in two coats to concrete, brick or stone masonry surfaces in all positions with base coat of 12 to 15 mm thick in C.M. 1:4 and rough cast treatment 12mm thick in proportion 1:1 1/2:3 including scaffolding and fourteen days curing complete.	78.00	Sqm		
9	Providing and laying machine cut machine polished machine cut Kota stone slabs 20 to 25 mm thick for treads and risers of steps and staircases, with rounded nosing for the treads on a bed of 1:4 cement mortar including cement float, filling joints with neat cement slurry, curing, polishing and cleaning etc. complete.	135.00	Sqm		
10	Providing Mirror polishing to Kota Stone including using all necessary stones and equipments cleaning, washing etc. complete. For Flooring	135.00	Sqm		
	Total				
	Taxes will be paid at actual at the prevailing time.				
	Net Total				