

UMIT/Accounts/2025-26 /630

January 19th, 2026

SUB: Quotation for Maintenance work of inspection chamber and Gully Trap with plumbing work at North East and North West side UMIT Building at SNDT Women's University, Juhu Campus.

Madam/Sir,

Sealed quotations are invited for Quotation for "Maintenance work of inspection chamber and Gully Trap with plumbing work at North East and North West side UMIT Building at SNDT Women's University, Juhu Campus." Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Principal Usha Mittal Institute of Technology SNDT Women's University" at Juhu campus on or before 23rd January 2026. Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop. Envelop may contains following documents in respective envelop:

A) Technical Bid

- i. Profile of the vendor
- ii. Work Experience Certificate from the concerned the organization where work has been executed.
- iii. GST Certificate
- iv. PAN Copy
- v. If GST is not applicable then declaration of the same.

B) Financial Bid

- vi. Mentioning including all taxes
- vii. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Regards,



Dr. Yogesh Nerkar

Principal

(Offer should filled on letter head)
Annexure A

To,

The Principal,
Usha Mittal Institute of Technology
SNDT Women's University,
Juhu Tara Road, Santacruz West, Mumbai - 400049

Sub: Quotation for Maintenance work of inspection chamber and Gully Trap with plumbing work at North East and North West side UMIT Building at SNDT Women's University, Juhu Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr.No.	Description of work	Qty.	Unit	Rate	Amount
1	Providing and constructing Brick Masonry Inspection Chamber 90cm x 45cm x 90cm including 1:4:8 cement concrete foundation 1:2:4 cement concrete channels half round G.S.W.pipes, Brick Masonry, plastering from inside and C.I. lid cover of 100 Kilogram with lid and frame fixed in cement concrete.	5.00	Nos		
2	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually , striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete. Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually , striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete.	5.020	Cum		
3	Providing and fixing 15cm x 10cm salt glazed stoneware gully trap in cement concrete 1:4:8 outside the building including cast iron grating in the sink, connecting glazed stoneware pipe, brick masonry chamber with cast iron lid and cast iron grating for the gully trap.	5.00	Nos		
4	Supplying C.I. chamber cover 100 kg. Heavey as per approved sample by the Engineer in charge with all lead and lifts etc complete and stacking wherever directed.	6.00	Nos		

5	Providing and laying in trenches 25 mm dai. uPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	29.00	Rmt		
6	Provision for service point for garden watering with 25mm brass valve etc.complete	1.00	AU		
7	Providing rough cast cement plaster externally in two coats with coloured cement finish to concrete/ brick/ stone masonry surfaces in all positions with base coat 12 to 15 mm. thick in C.M. 1:4 using gray cement and rough cast treatment 12 mm thick in proportion of 1:1 1/2:3 using colour pigment including scaffolding and fourteen days curing etc. complete.	77.55	Sqm		
8	Supply of Mazdoor-unskilled Heavy Male for cleaning of old chamber and carting away debris	36.00	Day		
9	Manually clearing the chokes from underground drainage line including Inspection chambers with the help of required tools for propre functioning line chamber to chamber etc. complete.	110.00	Rmt		
10	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for foundation and bedding / steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.),with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	6.00	Cum		
11	Providing and fixing 100 mm dia stabiliser pipe/ P.V.C. soil vent/waste pipe and with necessary fixtures and fitting such as bends, tees, single junctions, slotted vent, clamps etc. complete.	23.00	Rmt		
12	Providing and fixing 150mm dia stabilizer pipe/P.V.P.soil vent/waste pipe and with necessary fixtures and fitting such as bends, tees, single junctions, slotted vent, clamps etc. complete	5.00	Rmt		
13	Filling in plinth and floors with approved excavated material in 15cm. to 20cm. Layers including watering and compacting etc. complete.	1.00	AU		
	Total				
	Taxes will be paid at actual at the prevailing time.				
	Net Total				