

SNDT Women's University

1, Nathibai Thackersey Road,

Mumbai 400 020

Phone: +91 22 2203 1879

Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ

१, नाथीबाई ठाकरसी मार्ग

मुंबई ४०० ०२०

Telegram: UNIWOMEN

Website: sndt.ac.in

Estate Section/2026-27/167

25th August, 2026

SUB: Quotation for Repairs and Extension of canal road side compound wall from Karve Kutir to Parking area at SNDT Women's University, Pune campus.

Madam/Sir,

Sealed quotations are invited for Quotation for "Repairs and Extension of canal road side compound wall from Karve Kutir to Parking area at SNDT Women's University, Pune campus." Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before **07th September, 2026** Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop.

Envelop may contains following documents in respective envelop:

A) Technical Bid

- i. Detailed Company Profile (Contact details of contractor including address, phone number and email ID)
- ii. Copies of Work Completion Certificates / Work Orders for similar works executed in the last three years.
- iii. GST Registration Certificate (Self attested)
- iv. PAN Card (Self attested)
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant
- vii. Income Tax Return or Financial Statement of the last financial year or turnover 1.5 times of the civil work
- viii. Undertaking stating that the contractor has not been blacklisted by any Government / Semi-Government organization.

B) Financial Bid

- I. Mentioning including all taxes
- II. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Regards,

Prof. Vilas D. Nandavadekar

(Offer should filled on letter head)
Annexure A

To,

The Registrar,
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for Repairs and Extension of canal road side compound wall from Karve Kutir to Parking area at
SNDT Women's University, Pune campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description of work	Qty.	Unit	Rate	Amount
1	Removing wire fencing with iron/ C.C. fencing post and stacking the materials as directed with all leads, lifts etc. complete.	170.00	Rum		
2	Removing lime or lean cement concrete including stacking the spoils as directed with all leads, lifts etc, complete.	16.00	Cum		
3	Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/ granite/quartzite/gneiss metal for plain or molded sills, cornice, jambs, block in course, or architraves of required size and shapes including steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided,finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.) with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer etc. complete, With fine aggregate (Crushed sand VSI Grade)	12.00	Cum		
4	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete	39.00	Cum		
5	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in	408.00	Sqm		

	cement mortar 1:4 using waterproofing compound at 1Kilogramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.				
6	Providing and erecting 1.2 meter high wire fencing with five rows of barbed wire supported on mild steel angle (50 x 50x 6mm) post at 2.5 m c/c including excavation of pits of foundation concrete fixing the posts in (1:4:8) cement concrete block of 45x45x45 cm and fastening the Wires and painting the angles with one coat with red lead primer and two coats of oil painting etc.complete	170.00	Rmt		
	Total				
	Taxes will be paid at actual at the prevailing time.				
	Net Total				