



**SNDT WOMEN'S UNIVERSITY**  
1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

Estate Dept./2018-19/ (Not. 9)/201

November 12, 2018

**Sub: Quotation of Plaster and Painting work of Pump room and Electrical room at ground floor in Composite building at SNDT Women's University, Juhu Campus.**

**Madam/Sir,**

Sealed quotations are invited for Painting work of Pump room and Electrical room at ground floor in Composite building at SNDT Women's University, Juhu Campus. Interested vendors are to be submit their quote in the format given as Annexure A on company letter head. Quotation should be submitted to The Office of The Registrar at Churchgate campus on or before 29<sup>th</sup> November 2018.

**The University reserves the right to reject any or all quotations without assigning any reasons thereof.**

*Meena*  
15-11-18

**(Dr. Meena Kute)**  
**Registrar (Addl. Charge)**



**SNDT WOMEN'S UNIVERSITY**  
1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

Offer should filled on letter head)

**Annexure A**

To,  
The Registrar  
SNDT Women's University,  
Churchgate, Mumbai

**Sub: Quotation for Plaster and Painting work of Pump room and Electrical room at ground floor in Composite building at SNDT Women's University, Juhu Campus.**

**Respected Madam/Sir,**

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description	Qty	Unit	Rate	Amount
1	Providing internal cement plaster 25mm thick in two coats in cement mortar 1:4 without neeru finish, to concrete, brick or stone surfaces, in all positions including scaffolding and curing etc.complete.	250.00	Sqm.		
2	Providing and applying Two coats of wall care Putty of 2mm thickness for plastered surface and 5-6mm thickness finished concrete surface to Ceiling and Walls to prepare surface even and smooth of Brands BIRLA WHITE, BERGER, BISION, J.K., make, etc complete. b) For finished concrete walls/ceiling 5 to 6mm	500.00	Sqm.		
3	Providing and applying plastic emulsion paint of approved quality, colour and shade to new surface in three coats including scaffolding, preparing the surface. (excluding primer coat) etc. complete.	500.00	Sqm.		
4	Providing and applying priming coat on concrete/masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.	500.00	Sqm.		
5	Scrapping the old plastered internal surface with sand paper and coating the entire surface with mixture of whiting or glue and linseed on including scaffolding etc. complete. As directed.	500.00	Smt.		
	<b>Total Amount</b>				



**SNDT WOMEN'S UNIVERSITY**  
**1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020**

All the terms and conditions given in notifications are studied thoroughly and accepted fully.

Thanking You,

Yours Faithfully,

**Name of Company**  
**Signature of the Proprietor**  
**Date:**

**Note: Enclose GST number, PAN number, declaration if GST is not applicable.**

Sl. No.	Description	Qty	Unit	Rate	Amount
1	Providing internal cement plaster 25mm thick in two coats in cement mortar 1:4 without mesh fabric in concrete area of door window in all positions including scaffolding and curing etc complete.	120.00	sqm		
2	Providing and applying two coats of wall emulsion paint 2mm thickness on plastered surface and 2.5mm thickness finished concrete surface in Ceiling and walls. BRAN WHITE BERGOL 1500 LK. make etc complete. b) for finished concrete walls 1500 LK. 2 to 4mm.	300.00	sqm		
3	Providing and applying plastic emulsion paint of approved quality colour and shade to new surface in three coats including scaffolding, prepared the surface (excluding primer coat) etc complete.	200.00	sqm		
4	Providing and applying emulsion paint on concrete/ masonry/ plaster (cement plaster) surfaces including scaffolding if necessary, repairing the surface by thoroughly cleaning oil grease, dust and other foreign matter and sand paper etc repaired etc complete.	200.00	sqm		
5	Stripping the old plastered internal surface with sand paper and coating the surface with water proofing or glue and based on including scaffolding etc complete etc complete.	200.00	sqm		
<b>Total Amount</b>					